

PLOTTED/REVISED: 20-SEP-2019

DISTRICT \*: Metro  
 IPLOT NAME: Pay Item Tab Sheet  
 PATH & FILENAME: OTST\WorkZone\Templates\Title Sheets\Pay Item Tab Sheet.dgn

TRAFFIC CONTROL TABULATION																	TC	
TAB	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	NORTH					SOUTH									
				STAGE 1A	STAGE 1B	STAGE 2A	STAGE 2B PHASE 1	STAGE 2B PHASE 2	STAGE 1A	STAGE 1B	STAGE 2A PHASE 1	STAGE 2A PHASE 2	STAGE 2B PHASE 1	STAGE 2B PHASE 2	STAGE 3A	STAGE 3B	STAGE 4A	STAGE 4B
	PAVEMENT MARKING REMOVAL	LIN FT	136786	6281	11481	6400	11915	9841	1015		16974	46587	26292					
	PORTABLE PRECAST CONCRETE BARRIER DESIGN 8337	LIN FT	20266	1590	3850	900	900			700	12326							
	PORTABLE PRECAST CONCRETE BARRIER DESIGN 8337 - ANCHORED	LIN FT	1200								1200							
	RELOCATE PORTABLE PRECAST CONCRETE BARRIER DESIGN 8337	LIN FT	14036		800		900	900				9861	1575					
	RELOCATE PORTABLE PRECAST CONCRETE BARRIER DES 8337-ANCHORED	LIN FT	1200								1200							
(1)	IMPACT ATTENUATOR	ASSEMBLY	13	2	4	2	2			1	1		1					
(1)	RELOCATE IMPACT ATTENUATOR	ASSEMBLY	10		1		2	2			1	1	2	1				
	TEMPORARY GLARE SCREEN	LIN FT	12766		2600						10166							
	RELOCATE TEMPORARY GLARE SCREEN	LIN FT	10431								10431							
	TRAFFIC CONTROL SUPERVISOR	LUMP SUM	1															
	TRAFFIC CONTROL	LUMP SUM	1															
	ALTERNATE PEDESTRIAN ROUTE	LUMP SUM	1															
(2)	TC-A RAISED PAVEMENT MARKER TEMPORARY	EACH	2746	365	415	316	490	367	101	25	67		160		140	110	140	50
(3)	TC-A LINEAR DELINEATION PANEL	EACH	762		60						346	200	156					
(2)	TC-A MEDIAN BARRIER DELINEATOR	EACH	1845	53	305	27	55	30			735	640						
	DYNAMIC SPEED DISPLAY SIGN	EACH	4															
	PORTABLE CHANGEABLE MESSAGE SIGN	UNIT DAY	143		5	5		33	10	26	44				20			
	INTERIM PAVEMENT MARKING	LUMP SUM	1															
	TC-A REMOVABLE PREFORMED PAVEMENT MARKING TAPE	LIN FT	19856	3108	3069	1444	800	1023		1660	302		1950		1900	1400	2700	500
	REMOVABLE PREFORMED PLASTIC MASK (BLACK)	LIN FT	4129	260	620	289	160	200		200			200		400	400	1400	
	TC-A 4" SOLID LINE PAINT	LIN FT	112775	5971	9621	5750	10775	8427	1015		10381	36773	24062					
	TC-A 8" SOLID LINE PAINT	LIN FT	6052		810			670			2262	2310						
	TC-A 4" BROKEN LINE PAINT	LIN FT	15370	310	1050	650	1140	450			3560	5980	2230					
	TC-A 8" DOTTED LINE PAINT	LIN FT	2589					294			771	1524						

- (1) ATTENUATORS ARE TL-3 UNLESS NOTED OTHERWISE
- (2) ALL ONE WAY
- (3) TO BE PLACED ON TRANSITIONS AS DIRECTED BY PROJECT ENGINEER

TRAFFIC CONTROL ITEM COLOR																												TC-A				
ITEM DESCRIPTION	UNIT	NORTH												SOUTH																		
		STAGE 1A		STAGE 1B		STAGE 2A		STAGE 2B PHASE 1		STAGE 2B PHASE 2		STAGE 1A		STAGE 1B		STAGE 2A PHASE 1		STAGE 2A PHASE 2		STAGE 2B PHASE 1		STAGE 2B PHASE 2		STAGE 3A		STAGE 3B		STAGE 4A		STAGE 4B		
		WHITE	YELLOW	WHITE	YELLOW	WHITE	YELLOW	WHITE	YELLOW	WHITE	YELLOW	WHITE	YELLOW	WHITE	YELLOW	WHITE	YELLOW	WHITE	YELLOW	WHITE	YELLOW	WHITE	YELLOW	WHITE	YELLOW	WHITE	YELLOW	WHITE	YELLOW	WHITE	YELLOW	
RAISED PAVEMENT MARKER TEMPORARY	EACH	215	150	245	170	235	81	220	270	302	65	101		25		67				115	45			140		70	40	100	40	50		
LINEAR DELINEATION PANEL	EACH			30	30											73	273		200	50	106											
MEDIAN BARRIER DELINEATOR	EACH		53	122	183	27			55	30					306	429	330	310														
REMOVABLE PREFORMED PAVEMENT MARKING TAPE	LIN FT	1990	1118	1350	1719	1444			800	1023			1660		302				1950					1900		1000	400	2300	400	500		
4" SOLID LINE PAINT	LIN FT	3426	2545	5512	4109	2875	2875	5507	5268	6670	1757	1015			6091	4290	13975	22798	13087	10975												
8" SOLID LINE PAINT	LIN FT			810						670					2262				2310													
4" BROKEN LINE PAINT	LIN FT	310		1050		650		1140		450					3560				5980		2230											
8" DOTTED LINE PAINT	LIN FT									294					771				1524													

UPDATED 09/20/19

**PAY ITEM TABULATION SHEET**

DRAWN BY: \_\_\_\_\_ CHECKED BY: \_\_\_\_\_ CERTIFIED BY \_\_\_\_\_ LIC. NO. \_\_\_\_\_ DATE \_\_\_\_\_

STATE PROJ. NO. 0000-000 (TH 000) SHEET NO TCXXX OF TCXXX SHEETS